

**PACOFS Perimeter Fence BoQ**

DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
<p>BILL NO. 2</p> <p>ALTERATIONS (Provisional)</p> <p>SUPPLEMENTARY PREAMBLES</p> <p>View site</p> <p>Before submitting his tender the contractor shall visit the site and satisfy himself as to the nature and extent of the work to be done and the value of the materials contained in the buildings or portions of the buildings to be demolished. No claim for any variations of the contract sum in respect of the nature and extent of the work or of inferior or damaged materials will be entertained</p> <p>Explosives</p> <p>No explosives whatsoever may be used for demolition purposes unless otherwise stated</p> <p>General</p> <p>The contractor shall carry out the whole of the works with as little mess and noise as possible and with a minimum of disturbance to the occupants. He shall provide proper protection and provide, erect and remove when directed, any temporary tarpaulins that may be necessary during the progress of the works, all to the satisfaction of the Senior Manager Facilities</p> <p>Water supply pipes and other piping that may be encountered and found necessary to disconnect or cut, shall be effectually stopped off or grubbed up and removed, and any new connections that may be necessary shall be made with proper fittings, to the satisfaction of the Senior Manager Facilities</p> <p>The contractor will be required to take all dimensions affecting the existing buildings on the site and he will be held solely responsible for the accuracy of all such dimensions where used in the manufacture of new items (doors, windows, fittings, etc)</p> <p>REMOVAL OF EXISTING WORK</p> <p><u>Removing concrete pavers</u></p>				

DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
Taking out and removing concrete pavers and set aside for re-use	m3	101,7		
<u>Breaking up and removing steel Bolards</u>				
50x50mm Steel Bolards	No.	18		
Total Carried forward				